


photo #1


Filtre-presse

Camion de raclage

decoking truck

Possible place where we can place the trucks if required. Or we run pipe from original place. See Plot plan.





CODE DE SERVICE:		B-101	FOUR - TOUR SOUS VIDE	ORDRE	
AVIS	904790173	ARRÊT 2021		PLANIFICATION	60092903
				MATÉRIEL	
				TEMPS	

DESCRIPTION SOMMAIRE DES TRAVAUX:

Installer 2 bacs (contenaire) de récupérations

Installer échafaudage

Tourner les deux coudes vers l

Installer lanceurs receveurs

surface requise pour le lanceur et receveur est 12 pied carré.
élévation est de 24 pied

RÉV:

00



SAP#

100097046


CODE DE SERVICE

M10D031

DESCRIPTION

ATB DU C1068 VERS B0101

(O-1991-3"/4"-UD10)



ISOLÉ
010-O-1991-M-3/4
SEPT. 2005
D. MANGIALARDI

Rev. 0



SAP#

100097048


CODE DE SERVICE

M10D033

DESCRIPTION




ATB DU C1068 VERS B0101

(O-2002-3"/4"-UD10)



ISOLÉ
010-O-2002-M-3/4
SEPT. 2005
D. MANGIALARDI

Rev. 0



CODE DE SERVICE:		B-101	FOUR - TOUR SOUS VIDE	ORDRE	
AVIS	904790173	ARRÊT 2021		PLANIFICATION	60092903
				MATÉRIEL	
				TEMPS	

DESCRIPTION SOMMAIRE DES TRAVAUX:

Installer échafaudage

Enlever les deux coudes et tous instruments sur les tubes a décoker:

TE/TW-01464 ; TE/TW-01466; TE/TW-01468 et TE/TW-01469

Installer spool temporaire et bac de récupération

Installer lanceur receveur

Faire un rayon X sur les tubes après décoke

RÉV:


01

(O-1957-14"-UD14)


(O-1958-16"-UD14)

(O-1959-18"-UD14)

Entrance and exit for decoking radiant
B-101 (10"X#150 RF) QTY 1



3770



ISOLE

010-O-1957/1958-1

010-O-1959-1

MARS 2006


D.M.

Rev.01/2018-TP


(O-1950-14"-UD14)

(O-1951-16"-UD14)

(O-1952-18"-UD14)



3770



ISOLÉ

010-O-1950/1951-1

010-O-1952-1

MARS 2006

D.M.

Rev.01/2018-TP

POUR INSTALLATION
TEMPORAIRE

LISTE DE MATERIEL

No	QTE	DIA	DESCRIPTION	NORME / CODE
1	15'6"	10	Pipe, A106-B, SMLS, Sch Std, BBE	ASME B36.10M
2	4	10	WN Flg, A105N, CL300, Sch Std, RF	ASME B16.5

1	2018 13 NOV	DESSIN SPOOLS TEMPORAIRES EMIS POUR PLAN FINAL (60086947)	MeG	CFL	K. HAMDAN	
No.	DATE	REVISION	PAR	VERIF	ING. PROJET No. Enregistrement	APPR

	CONCEPTEUR	G. TREMBLAY (TUMEC)		
	DESSINATEUR	ME. GATINEAU		
	VERIFICATEUR	CHANFER LY		
	SUPERVISEUR ING.	S. ARCAND		
	DATE	2018-11-13		
UNITE 010 BRUT SPOOLS TEMPORAIRES POUR DECOKAGE B-101 B-101-DECOKE-001-MK1 & B-101-DECOKE-001-MK2		ECHELLE	AUCUNE	
		CLASSE	No. DE DESSIN	REV
		M	010-600B1479	1



NOTES:

1. REGIE RBQ: NON
2. LES DIMENSIONS EN CHANTIER DOIVENT ETRE VALIDEES AVANT FABRICATION.
3. INSTALLER UNE PLAQUE D'IDENTIFICATION EN SS SUR CHAQUE SPOOL ET Y INSCRIRE:
 - NO ISOMETRIQUE: 010-600B1479
 - NO SPOOLS: B-101-DECOKE-001-MK1 ET/OU B-101-DECOKE-001-MK2
 - SPEC: UD1
 - ANNEE DE FABRICATION
4. PEINDRE LES SPOOLS TEMPORAIRES DE COULEUR: ORANGE FLUORESCENT.

NO. DE CONDUITE		SUNCOR SPECIFICATION	PRODUIT	SYSTEME REVETEMENT	CODE DE COULEUR	ISOLATION ET TRACAGE	EPAISS. D'ISOLATION - MATERIEL		SUNCOR CLASSE INSPECTION / END	 CHANFREIN		
B-101-DECOKE-001-MK1 B-101-DECOKE-001-MK2		UD1	EAU, SODA, ASH	NC9	NOTE 4	N/A	N/A	-	N/A			
M.D.M.T.	PRESSON D'OPERATION	TEMPERATURE D'OPERATION	PRESSON DE CONCEPTION	TEMPERATURE DE CONCEPTION	PRESSON D'ESSAI	CODE DE SERVICE D'INSPECTION	TRAITEMENT THERMIQUE	ALLOCATION DE CORROSION	CODE DE FABRICATION ET REPARATION			
-20 °F	370 PSIG	120 °F	700 PSIG	170 °F	1050 PSIG	N/A	NON	0.0625	B31.3 2016	RT 10%		


for INFO


enlever les TE et
bride pleine par
Suncor



B-101

TRANSFER PIPINGS (CROSSOVER & JUMPER)





MK1 et Mk2
entrance/ exit
decoke RADIANT
10"-150RF# QTY 2

ITEM NO.	NO. REQ'D	DESCRIPTION	MATERIAL	LATEST ASTM SPECIFICATION/GRADE	REMARKS
101	2	PIPE 10" NPS SCH. 40 x 19'-9 7/8" L.G.	90C - 1Mo	A335 Gr P9	
102	2	PIPE 10" NPS SCH. 40 x 21'-9 7/8" L.G.	90C - 1Mo	A335 Gr P9	
103	2	PIPE 8" NPS SCH. 40 x 20'-1 7/8" L.G.	90C - 1Mo	A335 Gr P9	
104	2	PIPE 8" NPS SCH. 40 x 22'-5" L.G.	90C - 1Mo	A335 Gr P9	
105	2	PIPE 8" NPS SCH. 40 x 20'-8" L.G.	90C - 1Mo	A335 Gr P9	
106	2	PIPE 6" NPS SCH. 40 x 22'-3 15/16" L.G.	90C - 1Mo	A335 Gr P9	
107	8	PIPE 5" NPS SCH. 40 x 20'-9 9/16" L.G.	90C - 1Mo	A335 Gr P9	
108	6	PIPE 5" NPS SCH. 40 x 22'-9 9/16" L.G.	90C - 1Mo	A335 Gr P9	
109	2	PIPE 5" NPS SCH. 40 x 22'-8" L.G.	90C - 1Mo	A335 Gr P9	
110	ONE	PIPE 4" NPS SCH. 40 x 25'-9 7/16" L.G.	90C - 1Mo	A335 Gr P9	
111	ONE	PIPE 4" NPS SCH. 40 x 26'-5 7/16" L.G.	90C - 1Mo	A335 Gr P9	
112	48	PIPE 4" NPS SCH. 40 x 20'-11 7/8" L.G.	90C - 1Mo	A335 Gr P9	
113	48	PIPE 4" NPS SCH. 40 x 22'-11 7/8" L.G.	90C - 1Mo	A335 Gr P9	
114	ONE	PIPE 4" NPS SCH. 40 x 25'-5 7/16" L.G.	90C - 1Mo	A335 Gr P9	
115	ONE	PIPE 4" NPS SCH. 40 x 26'-1 7/8" L.G.	90C - 1Mo	A335 Gr P9	

NOTES:
1. ALL DIMENSIONS ARE IN FEET UNLESS NOTED OTHERWISE.
2. ALL ELEVATIONS ARE RELATIVE TO GRADE EL. 100'-0".
3. ALL WELD PREPARATIONS SHALL CONFORM TO AWS B 16.25 EXCEPT AS OTHERWISE NOTED ON THIS DRAWING. ALL WELDS SHALL BE FULL PENETRATION, U.G.O.
4. S-C=FIELD WELD, A=AS REQUIRED.
5. BE=BEVEL END, BW=BUTT WELD
6. BOLT HOLES IN FLANGES TO STRADDLE THE HORIZONTAL AND VERTICAL CENTERLINES UNLESS NOTED OTHERWISE.
7. ALL MATERIALS SHALL BE SEAMLESS UNLESS OTHERWISE NOTED.
8. INTERMEDIATE TUBESUPPORTS, PER FOLLOWING KTI DRAWINGS W112.2, FLANGE SURFACE FINISHES SHALL BE AS FOLLOWS:
a) SPIRAL-WOUND GASKETS SHALL HAVE A FLANGE FACE SURFACE FINISH OF 125 Ra TO 250 Ra.
b) SURFACE FINISH ROUGHNESS STANDARDS PER ASME B46.1
9. **XX-XXXX-XX** INDICATES SHIPPING MARK.




ITEM NO.	NO. REQ'D	DESCRIPTION	MATERIAL	LATEST ASTM SPECIFICATION/GRADE	REMARKS
116	48	RETURN BEND 180° 4" NPS S.R. SCH. 40	90C - 1Mo	A234 Gr WP9	
117	8	RETURN BEND 180° 5" NPS S.R. SCH. 40	90C - 1Mo	A234 Gr WP9	
118	2	RETURN BEND 180° 6" NPS S.R. SCH. 40	90C - 1Mo	A234 Gr WP9	
119	2	RETURN BEND 180° 8" NPS S.R. SCH. 40	90C - 1Mo	A234 Gr WP9	
120	2	CONCENTRIC REDUCER 5" x 4" NPS SCH. 40	90C - 1Mo	A234 Gr WP9	
121	2	CONCENTRIC REDUCER 6" x 5" NPS SCH. 40	90C - 1Mo	A234 Gr WP9	
122	2	CONCENTRIC REDUCER 8" x 6" NPS SCH. 40	90C - 1Mo	A234 Gr WP9	
123	2	CONCENTRIC REDUCER 10" x 8" NPS SCH. 40	90C - 1Mo	A234 Gr WP9	
124	2	FLANGE 10" NPS 300# RFWN, SCH. 40 BORE	90C - 1Mo	A182 Gr F9	
125	6	FLANGE 4" NPS 300# RFWN, SCH. 40 BORE	90C - 1Mo	A182 Gr F9	
126	2	PIPE 10" NPS SCH. 40 x 4'-6 1/8" L.G.	90C - 1Mo	A335 Gr P9	
127	8	PLATE 1" x 3' x 4'	90C - 1Mo	A387 Gr 9	
130	1	PIPE 4" NPS SCH. 40 x 2'-6 5/16" L.G.	90C - 1Mo	A335 Gr P9	
131	1	PIPE 4" NPS SCH. 40 x 3'-2 3/16" L.G.	90C - 1Mo	A335 Gr P9	
132	2	PIPE 4" NPS SCH. 40 x 22'-11 7/8" L.G.	90C - 1Mo	A335 Gr P9	
133	2	PIPE 4" NPS SCH. 40 x 20'-11 7/8" L.G.	90C - 1Mo	A335 Gr P9	

10. IN CASE OF CONTRADICTION BETWEEN BILL OF MATERIAL AND THE DRAWING, THE DRAWING SHALL GOVERN AND KTI SHALL BE DIRECTLY INFORMED.
11. WORK THIS DRAWING WITH GENERAL ARRANGEMENT DRAWING NO. 33063-000-DW-0119-001, 002, 003, 102 & 105.
12. FLANGE SURFACE FINISHES SHALL BE AS FOLLOWS:
a) SPIRAL-WOUND GASKETS SHALL HAVE A FLANGE FACE SURFACE FINISH OF 125 Ra TO 250 Ra.
b) SURFACE FINISH ROUGHNESS STANDARDS PER ASME B46.1
13. CANADIAN REGISTRATION No. D.6124.6
14. PRESSURE PARTS AND ASSEMBLY OF PRESSURE PARTS SHALL BE REGISTERED IN ACCORDANCE WITH REQUIREMENTS OF QUEBEC BOILERS BRANCH.

DESIGN DATA		UNITS	RADIANT PROCESS COIL
DESIGN PRESSURE (ELASTIC / RUPTURE)	PSIG		300 / 300
DESIGN METAL TEMPERATURE	°F		1026
CORROSION ALLOWANCE	INCH		0.125
WARM (HEAT & COLD)	PSIG		750
WARM (NOT & CORRODED)	PSIG		306
(HYDRO-TEST PRESSURE (SHOP)	PSIG		1125
(HYDRO-TEST PRESSURE (FIELD)	PSIG		1125
PNEU-TEST PRESSURE (SHOP)			---
PNEU-TEST PRESSURE (FIELD)			---
PREHEAT TREATMENT REQUIRED, MIN.	°F		100
POST WELD HEAT TREATMENT REQUIRED			YES
RADIOGRAPHING SHOP BUTT WELDS	%		100
RADIOGRAPHING FIELD BUTT WELDS	%		100
LIQUID PENETRANT BUTT WELDS	%		---
MAGNETIC PARTICLE BUTT WELDS	%		---
DIRECTION WEIGHT (ESTIMATED)	LB.		38000
WEIGHT FULL OF WATER (ESTIMATED)	LB.		59850
DESIGN BASIS	CODE		API 530
CONSTRUCTION AS PER			
INSPECTION BY			

KTI REQUESTORS
KTI, CLIENT AND/OR THEIR DESIGNATED REPRESENTATIVE
BANTREL/PETRO-CANADA
MONTREAL REFINERY
CANADA
PROJECT: **MONTREAL CRUDE RECONFIGURATION PROJECT**
DATE: **9/6/04**
REVISED: **7/26/04**
FOR CONSTRUCTION: **6/9/04**
APPROVAL: **4/16/04**
SCALE: **3/8"=1'** CAD:

DWG. TITLE: **GENERAL ARRANGEMENT RADIANT COIL SIDE ELEVATIONS VACUUM FEED HEATER ITEM No: B-101**
PROJECT NO. **33063**
DWG. NO. **33063-000-DW-0119-101**
REV. **2**
1990 Post Oak Blvd., Suite 200
Houston, Texas 77056
CONFIDENTIAL PROPERTY OF KINETICS TECHNOLOGY INTERNATIONAL



- NOTES:
1. FOR GENERAL NOTES AND TECHNICAL SUMMARY SEE DRAWING NO. 33063-000-DW-0119-001
 2. WORK THIS DRAWING WITH GENERAL ARRANGEMENT DRAWING NO. 33063-000-DW-0119-101 & 303



BANTREL/PETRO-CANADA											
MONTREAL REFINERY CANADA											
PROJECT: MONTREAL CRUDE RECONFIGURATION PROJECT											
REV	DESCRIPTION	DWN	CKD	SE	PE	PM	DM	DATE	SCALE	3/8"=1'	CAD
1	REVISED	JS	JWA	BC	NA	VSS	THIS	9/6/04			
0	FOR CONSTRUCTION	JS	JWA	BC	NA	JPE	THIS	6/9/04			
A	FOR APPROVAL	JS	DMT	BC	VM	VSS	THIS	4/16/04			

BANTREL/PETRO-CANADA				GENERAL ARRANGEMENT RADIANT COIL END ELEVATIONS VACUUM FEED HEATER ITEM No: B-101			
MONTREAL REFINERY CANADA				DWG. NO. 33063-000-DW-0119-102			
PROJECT: MONTREAL CRUDE RECONFIGURATION PROJECT				REV. 1			
CONFIDENTIAL PROPERTY OF KINETICS TECHNOLOGY INTERNATIONAL				1990 Post Oak Blvd., Suite 200 Houston, Texas 77056			

